

Declaration of the manufacturer

Carrying out and confirming the factory leak test on the plastic tank type series septic tanks - collecting cesspits for below ground installation

Leak test:

Within the scope of the permanent production monitoring (own checks by workers, monitoring by superiors and QA employees, as well as external monitoring by authorised experts), a leak test is carried out on every tank of the above-mentioned series. Weight, wall thickness and visual inspection are documented for each container.

A leak test with negative air pressure is carried out on a random basis.

In addition, tests are carried out by approved testing institutes, confirmed in test report no. B 31.10.698.01 MFPA Weimar.


This confirms the fulfilment of the requirements according to EN 12566-3,

Tab. 1, No. 2 - Watertightness.

The tanks are designed for installation in traffic areas of class A according to EN 124 (only accessible) and seepable subsoil. Before installation, the tanks must be checked to ensure that they are free of damage. A further check of the tightness is the responsibility of the installation company.

The specifications in the installation instructions must be observed.

Bischofswerda, 22.03.2021


Zweigniederlassung der Roth Werke GmbH
Drebritzer Weg 44, PF 12 44
01877 Bischofswerda
Tel.: 03594 / 77 41 0 Fax: 03594 / 77 41 24