

Declaration of the manufacturer

Carrying out and confirming the factory leak test on the plastic tank type series septic tanks - collecting cesspits for below ground installation

Leak test:

Within the scope of the permanent production monitoring (own checks by workers, monitoring by superiors and QA employees, as well as external monitoring by authorised experts), a leak test is carried out on every tank of the above-mentioned series. Weight, wall thickness and visual inspection are documented for each container.

A leak test with negative air pressure is carried out on a random basis.

In addition, tests are carried out by approved testing institutes, confirmed in test report no. B 31.10.698.01 MFPA Weimar.


This confirms the fulfilment of the requirements according to EN 12566-3,

Tab. 1, No. 2 - Watertightness.

The tanks are designed for installation in traffic areas of class A according to EN 124 (only accessible) and seepable subsoil. Before installation, the tanks must be checked to ensure that they are free of damage. A further check of the tightness is the responsibility of the installation company.

The specifications in the installation instructions must be observed.

Bischofswerda, 22.03.2021

 **Roth Umwelttechnik**
Zweigniederlassung der Roth Werke GmbH
Drebnitzer Weg 44, PF 12 44
01877 Bischofswerda
Tel.: 03594 / 77 41 0 Fax: 03594 / 77 41 24